

Section 01710

Site Cleanup

PART 1 - GENERAL

1.01 APPLICABILITY

- A. This section applies to project cleanup activities to be conducted throughout the entire duration of the Work.

PART 2 – PRODUCTS

(NOT USED)

PART 3 - EXECUTION

3.01 CLEANUP DURING WORK PROGRESS

- A. Proceed with construction cleanup as the Work progresses
  - 1. Remove mud, oil, grease, soil, gravel, trash, scrap, debris, and excess materials that are unsightly or may cause accidents to persons or properties.
  - 2. Properly store tools and materials when not in use away from trafficked areas.
- B. During the progress of the work, the construction areas shall be kept clean and all rubbish, surplus materials, and unneeded construction equipment shall be removed and all damages repaired so that the public and property owners will be inconvenienced as little as possible. Cleanup shall follow directly behind the progress of the Work.
- C. Contractor shall fill in all depressions and water pockets on public and private property caused by his operations; clean all drains, ditches and culverts which have been obstructed by his work; and, shall leave the site in a neat condition wherever his operations have disturbed existing conditions.

3.02 FINAL CLEANUP

- A. Final cleanup (including any property restoration, replacement or restitution per the Contract) shall be completed to the satisfaction of the right-of-way grantor, or any abutters, as well as to the satisfaction of any municipal or state authority which may be involved if in public right-of-way.

-- END OF SECTION --